

# Solicitation Amendment No. 001

То:	Date:
Prospective Bidder/Offeror:	July 14, 2011
Project Title:	Project No.:
Northline Parking Infrastructure Improvements	11-35
Description of Solicitation Amendment: The solicitation for Construction Services: Northline Parking Infrastructure Improvements is hereby amended as set forth herein.	
DESCRIPTION: Front: 1. Drawing Index updated to include 2009 Irrigation Record	rd Drawings added <b>for reference only</b> .
<u>Drawing revisions:</u> Drawing I1.00:  1) Added sheets L1.04, L1.05, and L1.06 to 8I1.00 – Drawing Index.	
Civil:  2. Wheelstops at Alief Campus are no longer available to be relocated to Northline Campus. Approximately 24 are to be relocated within Northline from the north sidewalk on Lyerly Street. They are currently set unanchored to prevent parking on the sidewalk. All other proposed wheelstops are to be provided new by Contractor.  Drawing revisions: Drawing C12.00:  1) Removed wheelstops from relocation table. Drawing C4.00: 2) Removed Alief wheelstops from note 11. Drawing C4.01: 3) Removed Alief wheelstops from note 3.	
Acknowledgement of Amendment No. 001 by:	Date:
Company Name (Bidder/Offerer):  Signed by:	
Name (Type or Print):	Title:
The state of the s	



Procurement Operations 3100 Main St. Houston, TX 77002

#### **Architecture:**

3. Masonry selections for pavilions provided to match existing masonry on-site.

## **Project Manual revisions:**

Section 09 00 00 - Finish Schedule:

- 1) Modular Brick: Acme Tulsa Valley #33 Velour.
- 2) Burnished Face CMU: Headwaters White Limestone #700.
- 3) Cast Stone: Siteworks Natural.
- 4) Mortar: Headwaters White Limestone verify w/ architect.
- 4. Paint Manufacturer and Grade clarified for Structural Steel.

#### **Project Manual revisions:**

Section 09 00 00 – Finish Schedule:

- 1) Alkyd Enamel for Structural Steel to also be PPG SunProof.
- 5. Spherical Bollard quantities and color selections revised for coordination with Metro: Bollards on red colored concrete landings to be Wausau B1 Grey. All others to remain B7 Brick Red.

#### Project Manual revisions:

Section 09 00 00 - Finish Schedule:

- 1) Added B1 Grey color.
  - Section 12 93 00 BL Site Furnishings Sphere Bollards: Product Information:
- 2) Quantity for additional color added and corrected for original color:
  - a. Thirteen (13) B7 Brick Red units.
  - b. Ten (10) B1 Grey units.
- 6. Waste Receptacle and Waste & Ash Receptacle quantities corrected. Notes for the North Pavilion locations Receptacles corrected. Notes have been added for two locations not previously noted.

#### **Drawing revisions:**

Drawing AS1.04:

1) Note added for WR located at south end of the main paver walkway on 1AS1.04 – South Parking Lot.

Drawing AS1.05:

2) Note added for WRA located east of the Bosque on 1AS1.05 – West Service Driveway.

Drawing AS1.13:

3) Corrected notes and leaders for Receptacles on 1AS1.13 – North Pavilion Plan.

#### **Project Manual revisions:**

Section 12 93 00 WR – Site Furnishings – Waste Receptacles: Product Information:

- 4) Quantity corrected:
  - a. Thirteen (13) units.

Section 12 93 00 WRA – Site Furnishings – Waste & Ash Receptacles: Product Information:

- 5) Quantity corrected:
  - a. Ten (10) units.
- 7. Reduce Seat quantities for Seats with Table by one to comply w/ TAS accessibility requirements.

# **Drawing revisions:**

Drawing AS1.05:

1) Deleted north Seat at center Table on 1AS1.05 – West Service Driveway

#### Project Manual revisions:

Section 12 93 00 ST – Site Furnishings – Seats With Table: Product Information:

- 2) Quantity for Seats:
  - a. Nineteen (19) units.



Procurement Operations 3100 Main St. Houston, TX 77002

8. Dimension corrected to match Metro's demolition of the east edge of the Main Parking Lot pavement.

Drawing revisions:

Drawing AS1.04:

1) Changed the dimension from the Sidewalk Easement to the back of curb to 7'-4" on 1AS1.04 (Metro was to demolish 8'-0", allowing 8" for proposed curb width shown in Civil detail). Dimensions for the three adjacent parking spaces at the north end clarified.

## Landscape:

9. Remove 5 proposed trees and all planting and irrigation from the area directly between HISD's temporary buildings and the HISD parking lot so area can be utilized by HISD.

#### **Drawing revisions:**

Drawing LP4.01:

- 1) Deleted the 5 northernmost Drake Elms (DE) along the main walkway from A1LP4.01;
- 2) Reduced the quantity of DE accordingly from C4LP4.01 Plant Schedule.

Drawing LI4.03:

3) Deleted the area's irrigation lines, heads, control valves, and sleeve from A1LI4.03;

Drawing LI6.01:

- 4) Reduced the quantity of irrigation heads and control valves accordingly from A1LI6.01.
- 10. Add hand watering by portable water tank for the 22 trees to be transplanted to the area west of the West Service Road that is not tied to irrigation system. Hand watering for these trees is to be included in the one year landscape maintenance plan.

Drawing LI1.01:

- 1) Note added to hand water on A1LI1.01.
- 11. Added 2009 Irrigation Record Drawings **for reference only**. These drawings show existing irrigation system as is best currently known, except for some sections in the new Right Of Way (ROW) along Fulton St already demolished by Metro with supply lines capped.

Added Drawings for reference:

- 1) L1.04.
- 2) L1.05.
- 3) L1.06.

#### **ATTACHMENTS:**

- 1. Drawings I1.00, C4.00, C4.01, C12.00, AS1.04, AS1.05, AS1.13, LP4.01, LI1.01, LI4.03, LI6.01, L1.04, L1.05, & L1.06.
- 2. Project Manual Sections 09 00 00, 12 93 00 BL, 12 93 00 WR, 12 93 00 WRA, & 12 93 00 ST.